

ADDENDUM NO. 1

Webster Street Improvements
Monroe, Nebraska
July 27, 2022

The Project Manual for the Webster Street Improvements in Monroe, Nebraska, dated July 11, 2022, is hereby revised as follows:

1. Paving the project in half width will be acceptable. The use of power screeds will be acceptable for equipment to be used for half width paving.
2. Contractors shall note that the paving dates shall work around the month of October. The project shall be completely done prior to October 1, or not started until after October 31.
3. The project shall not be left open during the winter months. All work shall either be completed before cold weather, or not started and completed during the 2023 spring construction season.
4. Contractors shall protect adjacent asphalt surfacing during construction. The use of planks, plywood, and other protective measures are encouraged to prevent damage to existing paving. Damage to adjacent surfaces during construction shall be repaired or replaced by the Contractor at no cost to the Owner.
5. Provide sealant and backing at concrete and asphalt joint.

END OF ADDENDUM NO. 1

